



MANHOLE NOTES:


1. MANHOLE STEPS ARE REQUIRED FOR ANY STRUCTURE DEEPER THAN 4 FEET AND SHALL CONFORM TO MATERIAL SPECIFICATION 725-02.01. THE COST OF THE STEPS SHALL BE INCLUDED IN THE PRICE BID FOR DROP INLETS OR MANHOLES.
2. MANHOLE TOP SLABS, FRAMES AND COVERS SHALL BE DESIGNED FOR H-25 LOADING.
3. MANHOLE FRAMES AND COVERS SHALL BE SYRACUSE CASTING NO. 1032 FRAME W/ NO. 1007 PLATEN COVER (VENTED) OR APPROVED EQUAL. PAYMENT AREA = 3.3 SQUARE FEET
4. INTERIOR AND EXTERIOR WALLS SHALL BE COATED WITH TWO COATS OF KOPPERS SUPER SERVICE BLACK OR APPROVED EQUAL. (AFTER BENCH INSTALLED)



MANHOLE FRAME & COVER
ITEM 655.01



M.H. TYPE	DIM. 'A'	DIM. 'B'	DIM. 'C'
"A"	4'-0"	24" MAX.	6'-0"
"B"	5'-0"	36" MAX.	7'-0"
"C"	6'-0"	48" MAX.	8'-0"



MANHOLE SECTION

MANHOLE TYPES "A", "B" AND "C"
NOT TO SCALE

4/1/98

REVISED